

# Wall Mount Termination Box

## Metal – 24 Port Double door



Wall-mounted fiber termination units are designed for fiber service splitting and termination in multi-dwelling units and small office environments with low to moderate port capacity. The enclosure features separate, lockable compartments for cable termination and splice (input) sections, ensuring secure access control and preventing unauthorized customer interference.

### Key Feature

- Supports up to 24 fiber ports (others available as per order)
- Pre-loaded with 24 SC/APC adaptors and pigtails
- Cable anchoring provision with included cable straps
- Integrated cable reeler for minimum bend radius control
- Optional splice tray provision
- Bottom cable entry & Radius-controlled cable routing
- Separate access for cable and splice tray sections
- Made of heat-resistant, high-impact plastic
- Suitable for FTTH deployments and PON applications.
- RoHS Compliant

## Product Specification

Wall Mount Material	Carbon Steel
Material Thickness	1.2mm to 1.5mm
Product Color	Siemens Gray / Black
Dimension (WxHxD)	530x410x100mm
Coupler Compatibility	SCA Simplex
Number of Ports	24 Max.
Number of Pigtails	24Nos
Type of Pigtail	Single Mode SCA
Insertion Loss	≤0.3dB
Return Loss	≥60dB
Operating Wavelength	1310nm & 1550nm
Max Supporting Cable Dia	14 to 16mm
No of Cable Input Port	2 Nos
No of Cable output Port	24 Nos (3mm Cable)
Ingress Protection	IP54

## Ordering Information

Part Number	Product Description
GXUWIB24SCADMY	Genius Network FTTX Wall Mount Box Double Door with 24F SC APC 1U with Pigtail